

# STANDARD FLY ASH CERTIFICATE



FINAL  
Prior Reports: None

Flyash Australia Pty Ltd  
ABN 68 002 840 271  
Head Office  
C/- Lindfield Corporate Centre  
Suite 18, 12 Tryon Road  
Lindfield NSW 2070  
Tel : (02) 9413 8422  
Fax: (02) 9413 84.32  
www.flyashaustralia.com.au

Certificate Number: CERT201047  
Issued: 21 May 2020

**Product being certified:** Bayswater - Microash Monthly Grab Fly Ash  
**Product sample date:** 04-May-2020  
**Sample Identification:** Sample Code: 20050411  
**Source Power Station:** Bayswater Power Station  
**Sample Condition:** Tested as Received. Testing Commenced on 11-May-2020  
**Certifying Laboratory:** Cement Australia - Darra Laboratory,  
18 Station Avenue, Darra Queensland 4076 Australia.

## Test Results

Test	Moisture %	Fineness @ 45 micron % Passed	Loss on Ignition %	Sulfuric Anhydride %	Available Alkali %	Chloride Ion %	Chemical Composition %
Result	0.1	97	0.4	0.1	n/a	0.001	97.2
Test Method	AS3583.2	AS3583.1	AS3583.3	AS2350.2	AS3583.12	AS3583.13	AS2350.2
AS 3582.1	0.5 % Maximum	85% Minimum	3.0 % Maximum	3.0 % Maximum	-	0.1 % Maximum	70% Minimum

Test	Relative Density	Relative Water Requirement %	Strength Index 7 Day Acc. %	Reference Cement Details
Result	2.30	91	136	Identification:: 20050487 Source: Goliath GP
Test Method	AS3583.5	AS3583.6	AS3583.6	Product Type: Type GP
AS 3582.1	-	-	Exceeds 105%	Sample Date: 12-May-20

## Additional Testing - Oxides

Test	CaO by XRF %	SiO <sub>2</sub> by XRF %	Al <sub>2</sub> O <sub>3</sub> by XRF %	Fe <sub>2</sub> O <sub>3</sub> by XRF %	SO <sub>3</sub> by XRF %	MgO by XRF %	Na <sub>2</sub> O by XRF %
Result	0.4	79.2	15.4	2.6	0.1	0.3	0.11
Test Method	AS2350.2	AS2350.2	AS2350.2	AS2350.2	AS2350.2	AS2350.2	AS2350.2

Test	K <sub>2</sub> O by XRF %	SrO by XRF %	TiO <sub>2</sub> by XRF %	P <sub>2</sub> O <sub>5</sub> by XRF %	Mn <sub>2</sub> O <sub>3</sub> by XRF %	Total Alkali (NaEQ) %
Result	0.95	<0.1	0.5	0.2	< 0.1	0.74
Test Method	AS2350.2	AS2350.2	AS2350.2	AS2350.2	AS2350.2	AS2350.2

This sample grade conforms to the following requirements of AS 3582.1:2016

Special	Grade 1	Grade 2
X	X	

**Approved Signatory**



A Prem  
Signatory - Cement Australia  
Chemical Testing  
Construction Materials Testing

Accredited for compliance with ISO/IEC  
17025 - Testing. The results of the tests,  
calibrations and/or measurements included in  
this document are traceable to  
Australian/national standards.



Cement Australia - Darra Laboratory  
NATA Accredited Laboratory Numbers  
187 188

ACCREDITED FOR  
**TECHNICAL  
COMPETENCE**

Notes:

